

9.0 RECOMMENDATION - ENFORCEMENT CONFIDENTIAL

I. Soil

- a) Based on our evaluation data and the site visit, DTSC recommends further investigation is warranted for the following SWMUs and AOCs identified in **Section 5** of this report.

SWMU NUMBER AND NAME

- 1 - SWMU No. 1. Tank Farm Area**
 - 1.1- Tank Farm**
 - 1.2- Sump Tank X508**
- 2 - SWMU No. 2. Process Area**
 - 2.1- Re-refinery**
 - 2.2- Mohawk treatment Area**
- 3 - SWMU No. 3. Wastewater Treatment Area- DAF Area**
 - 3.1- DAF Unit**
 - 3.2 -Tanks T-704A and T-704B**
- 4 - SWMU No. 4. West Loading/Unloading Area**
 - 4.1 - Bobtail Truck Loading/Unloading Area**
 - 4.2 - Transporting Truck Loading/Unloading Area**
- 5 - SWMU No. 5. Filter Wash Area**
- 6 - SWMU No. 6. Sump Tank X510**
- 7 - SWMU No. 7. Detention Sump 2**
- 8 - SWMU No. 8. Pumping and Valve Station West Tank Farm**
- 9 - SWMU No. 9. Pumping and Valve Station South Tank Farm**
- 10 - SWMU No.10. Pumping and Valve Station East Tank Farm**
- 11 - SWMU No. 11. Sump Tanks 453 and 454 Area**
 - 11.1- Sump Tank 453**
 - 11.2- Sump Tank 454**
- 12 - SWMU No. 12. Detention Sump 1**
- 13 - SWMU No. 13. Ten day transfer station area**

14 - SWMU No. 14. Railcar loading area 1

15 - SWMU No. 15. Underground Pipes, ditches and trenches

- b) Based on our evaluation, data, and technical knowledge at the Evergreen Facility, DTSC has recommended that additional information to be requested from the facility and additional site inspection to be conducted for the following AOCs to confirm that no further work is warranted and confirm that the potential for releases from these AOCs are low.

AOC Number	Name
1 - AOC No. 1	Raw Material and Product tanks
2 - AOC No. 2	Main Plant Storm Water-Outfall
3 - AOC No. 3	Discharges to Union Sanitation District connections – Lift Station
4 - AOC No. 4	Maintenance Shop
5 - AOC No. 5	Laboratory

Additional Data Needs for Soil

A Facility-wide investigation to identify contamination source areas if any is necessary.

II. Groundwater

Additional Data Needs for Groundwater

Groundwater monitoring should be performed at the entire Facility to assess the degree, extent and stability of contaminants, if any. If Groundwater contamination is confirmed, a comprehensive site-wide groundwater investigation will be necessary to identify onsite source areas, and to identify additional and/or unknown contaminants which might contribute to the degradation of groundwater underlying the general area if remedial action is not initiated.

If hazardous waste/material releases to soil and groundwater is confirmed as a result of facility-wide investigation, then:

- 1) Contaminated groundwater need to be stabilized as an interim measure; and
- 2) Its sources fully investigated and remediated under RCRA requirements.

III. Air

During the Facility expansion air monitoring should be conducted to monitor soil vapor and particulate matter from contaminated surfaces and soil if any.

10.0. REFERENCES


- US EPA, 1996a, Soil Screening Guidance: Fact Sheet, Office of Emergency Response, Washington, D.C., Publication 9355.4-14FSA, EPA/540/F-95/041, PB96-963501, July.
- US EPA, 1996b, Soil Screening Guidance: User's Guide, Office of Emergency Response, Washington, D.C., Publication 9355.4-23, Second Edition, July.
- US EPA, 1996c, Region 9, Preliminary Remedial Goals, S.J. Smucker, August 1.
- City of Newark, 2003, Negative Declaration and Initial Study
- ABAG, 1995, Projections 1996, Forecasts for the San Francisco Bay Area. December.
- Alameda County Public Health Department (ACPHD), 2001, Select Health Indicators For Cities In Alameda County. Community Assessment, Planning, And Education Unit, Health Care Services Agency
- ATSDR, 2002, Environmental Triggers of Asthma. Case Studies in Environmental Medicine. Course: SS3097, Date: April 2002.
- BAAQMD, 1991. AB 2588 Health Risk Assessment Guidelines: Supplemental Instructions and Comments. San Francisco.
- BAAQMD, 1999, BAAQMD CEQA Guidelines: Assessing the Air Quality Impacts of Projects and Plans. BAAQMD, April 1996, revised December.
- BAAQMD, 2001, Toxic Air Contaminant Control Program Annual Report: 2000. BAAQMD. December.
- Boore, Joyner, and Fumal, 1993, Estimation of response spectra and peak acceleration from western North American earthquakes: An interim report: U.S. Geological Survey, Open-file Report 93-509.
- City of Newark, 1992, General Plan Update Project 2007. June.
- Coltran R. S., Kumar, V., and Collins, T. 1999, Robbins Pathologic Basis of Disease. – 6th Ed.. W. B. Saunders Co., Philadelphia, PA.

- EPA, 1992, Environmental Priorities Initiative Preliminary Assessment. Prepared by Ecology and Environment, Inc.. March.
- GEI, 1985, Report, Soil investigation and paving design, proposed oil reprocessing plant, Smith Avenue and Southern Pacific Railroad, Newark, California: Prepared for Kinetics Technology International Corporation.
- Hart, E.W., Bryant, W.A., Manson, M.W., and Kahle, J.E., 1986, Summary report, fault evaluation program, 1979-1980 area (southern San Francisco Bay region): California Division of Mines and Geology, Open-File Report 81-3, 12p., 1 plate, scale 1:250,000.
- Hoose, S.N., 1987. The Morgan Hill earthquake, an overview; *in*, S.N. Hoose, ed., The Morgan Hill, California earthquake of April, 24, 1984: U.S. Geological Survey Bulletin 1639, pp. 1-14.
- Idriss, 1993, Procedures for selecting earthquake ground motions at rock sites: National Institute of Standards and Technology, NIST GCR 93-625.
- Jennings, C.W., 1994, Fault activity map of California and adjacent areas with locations and ages of recent volcanic eruptions: California Division of Mines and Geology, Geologic Data Map No. 6. Scale 1:750,000.
- National Cancer Institute, 2000, Surveillance, Epidemiology, and End Results (SEER) Cancer Statistics Review, 1973-1997. NCI. Bethesda, MD.
- Rogers, T.H. and Williams, J.W., 1974, Potential seismic hazards in Santa Clara County, California: California Division of Mines and Geology, Special Report 107, 39p.
- RWQCB, 1991, Water Quality Control Plan, San Francisco Bay Basin Region.
- Sadigh, et al., 1993, Specification of long period ground motions: Proceedings, ATC-17-1, Seismic Isolation Systems, Vol. 1.
- Sax, N.I., 1979. Dangerous Properties of Industrial Materials. 5th ed. Van Nostrand Reinhold Company. New York.


- Slemmons, D.B. and Chung, D.H., 1982. Maximum credible earthquake magnitudes for the Calaveras and Hayward fault zones, California: *in*, E.W. Hart, S.E. Hirschfeld, and S.S. Schulz, eds., Proceedings of the Conference on Earthquake Hazards in the Eastern San Francisco Bay Area: California Division of Mines and Geology, Special Publication 62, pp. 115 - 124.
- Soil Conservation Service, 1981, Soil Survey of Alameda County, Western Part: U.S. Department of Agriculture, 103p.
- Steinbrugge, K.V., Bennett, J.H., Lagorio, H.J., Davis, J.F., Borchardt, G., and Topozada, T.R., 1987. Earthquake planning scenario for a magnitude 7.5 earthquake on the Hayward fault in the San Francisco Bay Area: California Division of Mines and Geology, Special Publication 78. 242 pp.
- Topozada, T.R., Borchert, G., Hallstrom, C.L., and Youngs, L.G., 1992, Planning Scenario for a Major Earthquake on the Hayward fault: California Division of Mines and Geology, Special Publication 113, pp.457-462.
- United States Public Health Services, 1999, Respiratory Diseases, Healthy People 2010, Conference Edition.
- Wagner, D.L., Bortugno, E.J., and McJunkin, R.D., 1990, Geologic map of the San Francisco-San Jose Quadrangle: California Division of Mines and Geology, Regional Geologic Map Series, Map No. 5A. Scale 1:62,500.
- Wesson, R.L., Helley, E.J., Lajoie, K.R., and Wentworth, C.M., 1975. Faults and future earthquakes; *in* R.D. Borchardt, ed., Studies for Seismic Zonation of the San Francisco Bay Region: U.S. Geological Survey, Professional Paper 941-A, pp. A5 - A30.
- Working Group on California Earthquake Probabilities [WGCEP], 1990. Probabilities of large earthquakes in the San Francisco Bay Region, California: U.S. Geological Survey Circular 1053. 51 pp.

ATTACHMENT A

FIGUERS



Cargill Salt Ponds



CITY OF NEWARK

OFFICIAL ZONING MAP





Figure II-4
Zoning Map



INTERIOR - GEOLOGICAL SURVEY, RESTON, VIRGINIA - 1989

ROAD CLASSIFICATION

Primary highway
hard surface
Secondary highway
hard surface

Light-duty road, hard or
improved surface
Unimproved road

Interstate Route U.S. Route State Route

QUADRANGLE LOCATION

1	2	3
4	5	
6	7	8

1 San Leandro
2 Hayward
3 Dublin
4 Redwood Point
5 Niles
6 Palo Alto
7 Mountain View
8 Milpitas

ADJOINING 7.5' QUADRANGLE NAMES

FIGURE II-1

NEWARK, CA


1997

NIMA 1559 II SE-SERIES V895

ISBN 0-607-91586-2
9 780607 915860

ET
929
1Y 0.3048

NDARDS
VVER, COLORADO 80225
ABLE ON REQUEST



QUADRANGLE LOCATION

1	2	3
4		5
6	7	8

1 San Leandro
2 Hayward
3 Dublin
4 Redwood Point
5 Niles
6 Palo Alto
7 Mountain View
8 Milpitas

ADJOINING 7.5' QUADRANGLE NAMES

ROAD CLASSIFICATION

Primary highway
hard surface
Secondary highway
hard surface

Light-duty road, hard or
improved surface
Unimproved road

Interstate Route U.S. Route State Route

FIGURE II-1

NEWARK, CA


1997

NIMA 1559 II SE-SERIES V895



27
129
Y 0.3048

4DARDS
IVER, COLORADO 80225
ABLE ON REQUEST




= Four way traffic signal with designated, signal controlled turning lanes.



= Four way stop sign with designated turning lanes.

Figure II-8



Evergreen Existing (Unexpanded) and Proposed (Expanded)
Used Oil Management Summary





Figure III-2


Revised January 2004



Revised January 2004

Figure III-3a

*Evergeen Wastewater Treatment Summary
Existing (Unexpanded) Facility*



Revised January 2004

Figure III-3b

DSJF-016

*Evergreen Waste Water Treatment Summary
Proposed (Expanded) Facility*

EVERGREEN OIL, INC.
RCRA FUEL BLENDING





Figure III-4

Revised - January 2004

Evergreen Consolidation and Transfer System



Note: RCRA and Non-RCRA wastes will not be mixed.




Figure III-5
Revision 0 – January 2004

EVERGREEN OIL INC.
OVERVIEW OF WASTE CHARACTERIZATION




FIGURE III-6

**FIGURE III-7: DECISION TREE FOR
USED OIL MANAGEMENT**





FIGURE III-8: DECISION TREE FOR
USED OIL MANAGEMENT
FEED TO REFINERY



EOI RCRA Part B Permit Application
Revision 0 – January, 2004

FIGURE III-9: DECISION TREE FOR
USED OIL MANAGEMENT

NON-RCRA WASTE OIL INCLUDING CONTAMINATED PETROLEUM PRODUCTS FOR FUEL OIL
BLENDING




FIGURE III-10a: DECISION TREE FOR
WASTE WATER TREATMENT PLANT (WWTP)




FIGURE III-10a (Cont.): DECISION TREE FOR
WASTE WATER TREATMENT SYSTEM(WWTP)




FIGURE III-10b: DECISION TREE FOR
WASTE WATER TREATMENT SYSTEM(WTS-DAF)




FIGURE III-10b (Cont.): DECISION TREE FOR
WASTE WATER TREATMENT SYSTEM(WTS-DAF)




FIGURE III-11: DECISION TREE FOR
RCRA FUEL OIL BLENDING




FIGURE III-11(Cont.): DECISION TREE FOR
RCRA FUEL OIL BLENDING




FIGURE III-12: DECISION TREE FOR
CONSOLIDATION & TRANSFER





FIGURE III-12(Cont.): DECISION TREE FOR
CONSOLIDATION & TRANSFER



ATTACHMENT B

TANK AND EQUIPMENTS TABLES

January 2004

Table IV-1
Existing and Proposed Hazardous Waste and Products Tanks

Existing Tank Number	Existing Contents/Usage	Useable Capacity (Gal.)	Total Capacity (Gal.)	Proposed Tank Number	Proposed Contents/Usage
T-501A	Used Oil	9,158	10,000	T-512B	Used Oil
T-501B	Used Oil	9,158	10,000	T-512C	Used Oil
T-501C	RCRA Fuels	9,158	10,000	T-800	RCRA Fuels
T-501D	Waste Antifreeze	24,532	25,000	T-500	Waste Antifreeze
T-512A	Used Oil	9,158	10,000	T-651C	Used Oil
T-512B	Used Oil	9,158	10,000	T-512A	Used Oil
T-502	Used Oil Fuel Blending	47,632	50,000	T-502	Oily Waste
T-503A	Recycled Oil	192,993	200,000	T-503A	Recycled Oil
T-503B	Recycled Oil	192,993	200,000	T-503B	Recycled Oil
---	---	192,993	200,000	T-503C	Recycled Oil
T-504	Lube Distillate	47,632	50,000	T-508C	Base Oil Rundown
T-505	Used Oil Fuel Blending	47,632	50,000	T-505	Used Oil Fuel Blending
T-506A	Lube Oil/100 N	47,632	50,000	T-506A	Used Oil Fuel Blending
T-506B	Lube Oil/100 N	47,632	50,000	T-508D	Base Oil Rundown
T-506C	Lube Oil/100 N	47,632	50,000	T-506B	Used Oil Fuel Blending
T-506D	Lube Oil/100 N	47,632	50,000	T-508B	Base Oil Rundown
T-507	Used Oil Fuel Blending	47,632	50,000	T-507	Used Oil Fuel Blending
T-508	Lube Oil/100 N	47,632	50,000	T-508A	Base Oil Rundown
T-509	Used Oil Fuel Blending	24,532	25,000	T-509	Used Oil Fuel Blending
T-510	RGO Rundown	24,532	25,000	T-510	RGO Rundown
T-511A	Asphalt	35,034	35,285	T-511A	Asphalt Flux
T-511B	Asphalt	35,034	35,285	T-511B	Asphalt Flux
---	---	35,034	35,285	T-511C	Asphalt Flux
T-651A	Used Oil	30,514	31,000	T-651A	Non-RCRA Oily Water
T-651B	Used Oil	30,514	31,000	T-651B	Non-RCRA Oily Water
T-652	Used Oil	9,158	10,000	T-652	Non-RCRA Oily Water
T-705A	Treated Wastewater	6,624	7,000	---	---
T-705B	Treated Wastewater	6,624	7,000	---	---
T-705C	Treated Wastewater	6,624	7,000	---	---
T-706	Treated Wastewater		12,000	---	---
---	---	47,632	50,000	T-506C	Used Oil Fuel Blending
---	---	47,632	50,000	T-506D	Used Oil Fuel Blending
---	---	47,632	50,000	T-506E	Used Oil Fuel Blending
---	---	47,632	50,000	T-506F	Used Oil Fuel Blending
---	---	4,136	4,500	T-501A	Used Oil
---	---	4,136	4,500	T-501B	Used Oil
---	---	4,136	4,500	T-501C	Used Oil
---	---	4,136	4,500	T-501D	Used Oil
---	---	4,136	4,500	T-501E	Used Oil
---	---	4,136	4,500	T-501F	Used Oil
---	---	4,136	4,500	T-501G	Used Oil
---	---	4,136	4,500	T-501H	Used Oil
---	---	4,136	4,500	T-501I	Used Oil

January 2004

---	---	4,136	4,500	T-501J	Used Oil
---	---	24,532	25,000	T-513	Halogenated Overhead RCRA Waste
T-704A	Treated Wastewater	6,650	7,000	T-704A	Treated Wastewater (WTS-DAF)
T-704B	Treated Wastewater	5,890	6,200	T-704B	Treated Wastewater (WTS-DAF)
---	---	10,000	10,000	TA-1201	Wastewater (WWTP)
---	---	7,000	7,000	TA-1202	Wastewater (WWTP)
---	---	7,000	7,000	TA-1203	Wastewater (WWTP)
---	---	7,000	7,000	TA-1204	Wastewater (WWTP)
---	---	7,000	7,000	TA-1205	Wastewater (WWTP)
---	---	6,000	6,000	TA-1206	Waste Oily
---	---	6,000	6,000	TA-1207	Wastewater (WWTP)
---	---	20,000	20,000	TA-1208	Treated Wastewater (WWTP)
---	---	20,000	20,000	TA-1209	Treated Wastewater (WWTP)
---	---	20,000	20,000	TA-1210	Treated Wastewater (WWTP)
---	---	20,000	20,000	TA-1211	Treated Wastewater (WWTP)
---	---	500	500	TA-1217	Treated Wastewater (WWTP)
		6,000	6,000	TA-1218	Wastewater
		6,000	6,000	TA-1219	Wastewater
		6,000	6,000	TA-1221	Sludge (WWTP)
			150,000	T-514A	Lube Oil
			150,000	T-514B	Lube Oil
			150,000	T-514C	Lube Oil
			150,000	T-514D	Lube Oil
			25,000	TG-A	Virgin Ethylene Glycol
			25,000	TG-B	Virgin Ethylene Glycol
			25,000	TG-C	Virgin Ethylene Glycol
	Tank Does Not Contain Hazardous Waste				
	Tank Contains Hazardous Waste				

Tank Usage Notes:

General Note: Tank numbers are generally grouped by designated use, both in the existing and the proposed facility. When the facility is expanded, the designated use of several tanks will change, necessitating the renumbering of the tanks. A description of the changes is provided below. Tanks which will be converted from non-hazardous usage to storage of hazardous wastes will be certified for hazardous waste usage in accordance with 22 CCR 66464.192 prior to use for hazardous waste storage.

The following tanks will change service:

- 1 – T-501C now stores halogenated RCRA fuel with the new permit it will store RCRA Fuels
- 2 – Tanks T-506 A & C will change from non-hazardous to hazardous service.
- 3 - Tanks 705 A/B/C and Tank T-706 stores non-hazardous water and will be removed with the new project.

TABLE IV-1A

Evergreen Oil Inc. Existing Facility

Existing Hazardous Waste Tanks

	Existing Tank Number			Total Capacity (Gal.)
1	T-501A	Used Oil	Existing	10,000
2	T-501B	Used Oil	Existing	10,000
3	T-501C	RCRA Fuel	Existing	10,000
4	T-501D	Waste Antifreeze	Existing	25,000
5	T-512A	Used Oil	Existing	10,000
6	T-512B	Used Oil	Existing	10,000
7	T-502	Used Oil Fuel Blending	Existing	50,000
8	T-503A	Used Oil Fuel Blending	Existing	200,000
9	T-505	Used Oil Fuel Blending	Existing	50,000
10	T-507	Used Oil Fuel Blending	Existing	50,000
11	T-509	Used Oil Fuel Blending	Existing	25,000
12	T-651A	Used Oil	Existing	31,000
13	T-651B	Used Oil	Existing	31,000
14	T-652	Used Oil	Existing	10,000

522,000

Existing Product Tanks

1	T-503B	Existing	Recycled Oil	200,000
2	T-504	Existing	Lube Distillate	50,000
3	T-506A	Existing	Lube Oil/100 N	50,000
4	T-506B	Existing	Lube Oil/100 N	50,000
5	T-506C	Existing	Lube Oil/100 N	50,000
6	T-506D	Existing	Lube Oil/100 N	50,000
7	T-508	Existing	Lube Oil/100 N	50,000
8	T-510	Existing	RGO Rundown	25,000
9	T-511A	Existing	Asphalt Flux	35,285
10	T-511B	Existing	Asphalt Flux	35,285

595,570

1,117,570

TABLE IV-1B

Evergreen Oil Inc. Expanded Facility (w/o WWTP Tanks)

Proposed Hazardous Waste Tanks

	Proposed Tank Number			Total Capacity (Gal.)
1	T-512B	Used Oil	Existing	10,000
2	T-512C	Used Oil	Existing	10,000
3	T-800	RCRA Fuels	Existing	10,000
4	T-500	Antifreeze	Existing	25,000
5	T-651C	Used Oil	Existing	10,000
6	T-512A	Used Oil	Existing	10,000
7	T-502	Oily Waste	Existing	50,000
8	T-505	Used Oil Fuel Blending	Existing	50,000
9	T-506A	Used Oil Fuel Blending	Existing	50,000
10	T-506B	Used Oil Fuel Blending	Existing	50,000
11	T-507	Used Oil Fuel Blending	Existing	50,000
12	T-509	Used Oil Fuel Blending	Existing	25,000
13	T-651A	Non-RCRA Oily Water	Existing	31,000
14	T-651B	Non-RCRA Oily Water	Existing	31,000
15	T-652	Non-RCRA Oily Water	Existing	10,000
16	T-501A	Used Oil	New	4,500
17	T-501B	Used Oil	New	4,500
18	T-501C	Used Oil	New	4,500
19	T-501D	Used Oil	New	4,500
20	T-501E	Used Oil	New	4,500
21	T-501F	Used Oil	New	4,500
22	T-501G	Used Oil	New	4,500
23	T-501H	Used Oil	New	4,500
24	T-501I	Used Oil	New	4,500
25	T-501J	Used Oil	New	4,500
26	T-506C	Used Oil Fuel Blending	New	50,000
27	T-506D	Used Oil Fuel Blending	New	50,000
28	T-506E	Used Oil Fuel Blending	New	50,000
29	T-506F	Used Oil Fuel Blending	New	50,000
30	T-513	Halogenated/RCRA Fuel	New	25,000

Total

692,000

Proposed Product Tanks

1	T-503A	Existing	Recycled Oil	200,000
2	T-503B	Existing	Recycled Oil	200,000
3	T-503C	New	Recycled Oil	200,000
4	T-508C	Existing	Base Oil Rundown	50,000
5	T-508D	Existing	Base Oil Rundown	50,000
6	T-508B	Existing	Base Oil Rundown	50,000
7	T-508A	Existing	Base Oil Rundown	50,000
8	T-510	Existing	RGO Rundown	25,000
9	T-511A	Existing	Asphalt Flux	35,285
10	T-511B	Existing	Asphalt Flux	35,285
11	T-511C	New	Asphalt Flux	35,285
12	T-514A	New	Lube Oil	150,000
13	T-514B	New	Lube Oil	150,000
14	T-514C	New	Lube Oil	150,000
15	T-514D	New	Lube Oil	150,000

Total

1,530,855

TANK DATA SHEET

Existing Hazardous Waste Storage or Treatment Tank

Tank No. T-501A)
Designated Use: Bobtail Preselection

1. Tank Information
 - a. Design Specifications
 1. Referenced design standard UL 142
 2. Dimensions (Diameter and Height (ft)) 11'11" x 12'0"
 3. Capacity (gallons) 10,000
 4. Shell thickness (inches) and corrosion allowance 3/16"
1/8"
 5. Pressure rating
Design (psig) Atmospheric
Operating (psig) Atmospheric
 6. Structural Supports Bolted to Concrete Slab
 7. Roof design Conical
 8. Year constructed 1985
 9. Tank location Outside
 10. Tank orientation Vertical
 - b. Construction Materials Steel (A-36)
 - c. Lining Material
 1. Composition None
 2. Thickness None
 3. Extent of coverage N/A
 - d. Corrosion/erosion resistance
 1. To wastes Steel is compatible with noncorrosive oily wastes
 2. To weather Paint should provide adequate protection
 - e. Pertinent Characteristics
 1. Date tank went into service 1986
 2. Life expectancy of tank (years) 20+ years starting 2001 See CONAM Inspection Report 12/03/01
 - f. Previous Use of Tank
 1. Material stored New 1986, waste oil stored since new
 2. Length of service 10 years
 - g. Drawing Certified by Engineer
2. Foundation Design Specifications
 - a. Foundation Material Con
 - b. Load Bearing Capacity
 - c. Fire Protection Rating Not stated, but design certified by registered engineer
 - d. Impact of Weather Tank design certified by registered engineer
 - e. Drawing Certified by Engineer
3. Ancillary Tank Equipment
 - a. Piping
 - 1) Feed 4"
 - 2) Discharge 6"



EOI RCRA Part B Permit Application
Revision 4 – August 2003

- | | | |
|----|---------------------------------------|--|
| b. | Instrumentation | High level alarm |
| c. | Process Flow Diagram | |
| d. | Feed Systems | |
| e. | Waste Feed Cutoff | Manual |
| f. | Bypass System | Overflow to X-508 |
| g. | Pressure Control | Vented to VRS |
| h. | Temperature Control | Operated at ambient temperature |
| i. | Liquid Level Indicators | Gage/board system on tank |
| j. | Vapor Control System and Tank Venting | Vented to VRS |
| k. | Labels Identifying Contents | NFPA and Tank No. |
| l. | Joints | Welded seams |
| m. | Welds | External |
| n. | Plumbing | |
| o. | Pumps | |
| p. | Pumping Rates | |
| q. | Lightning Protection | None |
| r. | Other Features | |
| | | |
| 4. | Waste Stored and Impact | |
| a. | Type and Characteristics | Used Oil/Recycled Oil |
| b. | S.G. of Wastes | .8 to 1.1 |
| c. | Layers of Wastes | 3 separate phases possible |
| d. | Compatibility With Tank or Liner | Wastes are fully compatible with tank. |



TANK DATA SHEET

Existing Hazardous Waste Storage or Treatment Tank

Tank No. T-501B
Designated Use: Bobtail Preselection

1. Tank Information
 - a. Design Specifications
 1. Referenced design standard UL 142
 2. Dimensions (Diameter and Height (ft)) 11'11" x 12'0"
 3. Capacity (gallons) 10,000
 4. Shell thickness (inches) and corrosion allowance 3/16"
1/8"
 5. Pressure rating
Design (psig) Atmospheric
Operating (psig) Atmospheric
 6. Structural Supports Bolted to Concrete Slab
 7. Roof design Conical
 8. Year constructed 1985
 9. Tank location Outside
 10. Tank orientation Vertical
 - b. Construction Materials Steel (A-36)
 - c. Lining Material
 1. Composition None
 2. Thickness None
 3. Extent of coverage N/A
 - d. Corrosion/erosion resistance
 1. To wastes Steel is compatible with noncorrosive oily wastes
 2. To weather Paint should provide adequate protection
 - e. Pertinent Characteristics
 1. Date tank went into service 1986
 2. Life expectancy of tank (years) 20+years starting 2001 See CONAM Inspection Report 12/03/01,
 - f. Previous Use of Tank
 1. Material stored New 1986, waste oil stored since new
 2. Length of service 10 years
 - g. Drawing Certified by Engineer
2. Foundation Design Specifications
 - a. Foundation Material Con
 - b. Load Bearing Capacity
 - c. Fire Protection Rating Not stated, but design certified by registered engineer
 - d. Impact of Weather Tank design certified by registered engineer
 - e. Drawing Certified by Engineer
3. Ancillary Tank Equipment
 - a. Piping
 - 1) Feed 4"
 - 2) Discharge 6"



EOI RCRA Part B Permit Application
Revision 4 – August 2003

b.	Instrumentation	High level alarm
c.	Process Flow Diagram	
d.	Feed Systems	
e.	Waste Feed Cutoff	Manual
f.	Bypass System	Overflow to X-508
g.	Pressure Control	Vented to VRS
h.	Temperature Control	Operated at ambient temperature
i.	Liquid Level Indicators	Gage/board system on tank
j.	Vapor Control System and Tank Venting	Vented to VRS
k.	Labels Identifying Contents	NFPA and Tank No.
l.	Joints	Welded seams
m.	Welds	External
n.	Plumbing	
o.	Pumps	
p.	Pumping Rates	
q.	Lightning Protection	None
r.	Other Features	
4.	Waste Stored and Impact	
a.	Type and Characteristics	Used Oil/Recycled Oil
b.	S.G. of Wastes	.8 to 1.1
c.	Layers of Wastes	3 separate phases possible
d.	Compatibility With Tank or Liner	Wastes are fully compatible with tank.



TANK DATA SHEET

Existing Hazardous Waste Storage or Treatment Tank

Tank No. T-501C
Designated Use: V-401/RCRA Fuel

1. Tank Information

a. Design Specifications

- | | | |
|-----|---|-------------------------|
| 1. | Referenced design standard | UL 142 |
| 2. | Dimensions (Diameter and Height (ft)) | 11'11" x 12'0" |
| 3. | Capacity (gallons) | 10,000 |
| 4. | Shell thickness (inches)
and corrosion allowance | 3/16"
1/8" |
| 5. | Pressure rating | |
| | Design (psig) | Atmospheric |
| | Operating (psig) | Atmospheric |
| 6. | Structural Supports | Bolted to Concrete Slab |
| 7. | Roof design | Conical |
| 8. | Year constructed | 1985 |
| 9. | Tank location | Outside |
| 10. | Tank orientation | Vertical |

b. Construction Materials

Steel (A-36)

c. Lining Material

- | | | |
|----|--------------------|------|
| 1. | Composition | None |
| 2. | Thickness | None |
| 3. | Extent of coverage | N/A |

d. Corrosion/erosion resistance

- | | | |
|----|------------|---|
| 1. | To wastes | Steel is compatible with noncorrosive oily wastes |
| 2. | To weather | Paint should provide adequate protection |

e. Pertinent Characteristics

- | | | |
|----|---------------------------------|--|
| 1. | Date tank went into service | 1986 |
| 2. | Life expectancy of tank (years) | 20 years (to be adjusted, based on periodic integrity testing) |

f. Previous Use of Tank

- | | | |
|----|-------------------|--------------------------------------|
| 1. | Material stored | New 1986, waste oil stored since new |
| 2. | Length of service | 10 years |

g. Drawing Certified by Engineer

2. Foundation Design Specifications

a. Foundation Material

Con

b. Load Bearing Capacity

c. Fire Protection Rating

Not stated, but design certified by registered engineer

d. Impact of Weather

Tank design certified by registered engineer

e. Drawing Certified by Engineer

3. Ancillary Tank Equipment

a. Piping

- | | | |
|----|-----------|----|
| 1) | Feed | 4" |
| 2) | Discharge | 6" |

b. Instrumentation

High level alarm



EOI RCRA Part B Permit Application
Revision 4 - May 2003

- | | | |
|----|---------------------------------------|--|
| c. | Process Flow Diagram | |
| d. | Feed Systems | |
| e. | Waste Feed Cutoff | Manual |
| f. | Bypass System | Overflow to X-508 |
| g. | Pressure Control | Vented to atmosphere |
| h. | Temperature Control | Operated at ambient temperature |
| i. | Liquid Level Indicators | Gage/board system on tank |
| j. | Vapor Control System and Tank Venting | Vented to atmosphere |
| k. | Labels Identifying Contents | NFPA and Tank No. |
| l. | Joints | Welded seams |
| m. | Welds | External |
| n. | Plumbing | |
| o. | Pumps | |
| p. | Pumping Rates | |
| q. | Lightning Protection | None |
| r. | Other Features | |
| 4. | Waste Stored and Impact | |
| a. | Type and Characteristics | V-401/RCRA Fuels |
| b. | S.G. of Wastes | .8 to 1.1 |
| c. | Layers of Wastes | 3 separate phases possible |
| d. | Compatibility With Tank or Liner | Wastes are fully compatible with tank. |



TANK DATA SHEET

Existing Hazardous Waste Storage or Treatment Tank

Tank No. T-501D
Designated Use: Waste Antifreeze Storage

1. Tank Information

a. Design Specifications

- | | | |
|-----|---|-------------------------|
| 1. | Referenced design standard | UL 142 |
| 2. | Dimensions (Diameter and Height (ft)) | 13'6" x 24'0 " |
| 3. | Capacity (gallons) | 25,000 |
| 4. | Shell thickness (inches)
and corrosion allowance | 3/16"
1/8" |
| 5. | Pressure rating | |
| | Design (psig) | Atmospheric |
| | Operating (psig) | Atmospheric |
| 6. | Structural Supports | Bolted to Concrete Slab |
| 7. | Roof design | Conical |
| 8. | Year constructed | 1985 |
| 9. | Tank location | Outside |
| 10. | Tank orientation | Vertical |

b. Construction Materials

Steel (A-283C)

c. Lining Material

- | | | |
|----|--------------------|------|
| 1. | Composition | None |
| 2. | Thickness | None |
| 3. | Extent of coverage | N/A |

d. Corrosion/erosion resistance

- | | | |
|----|------------|--|
| 1. | To wastes | Steel is compatible with ethylene glycol solutions |
| 2. | To weather | Paint should provide adequate protection |

e. Pertinent Characteristics

- | | | |
|----|---------------------------------|---|
| 1. | Date tank went into service | 1986 |
| 2. | Life expectancy of tank (years) | 20+years Starting 2001 See CONAM Inspection Report 12/03/01 |

f. Previous Use of Tank

- | | | |
|----|-------------------|--|
| 1. | Material stored | New 1986, contained waste oil until 1992 |
| 2. | Length of service | 10 years |

g. Drawing Certified by Engineer

2. Foundation Design Specifications

- | | | |
|----|-------------------------------|---|
| a. | Foundation Material | Concrete slab |
| b. | Load Bearing Capacity | |
| c. | Fire Protection Rating | Not stated, but design certified by registered engineer |
| d. | Impact of Weather | Tank design certified by registered engineer |
| e. | Drawing Certified by Engineer | |

3. Ancillary Tank Equipment

a. Piping

- | | | |
|----|-----------|----|
| 1) | Feed | 4" |
| 2) | Discharge | 6" |



EOI RCRA Part B Permit Application
Revision 4 – August 2003

- | | | |
|----|---------------------------------------|--|
| b. | Instrumentation | High level alarm |
| c. | Process Flow Diagram | |
| d. | Feed Systems | |
| e. | Waste Feed Cutoff | Manual |
| f. | Bypass System | Overflow to X-508 |
| g. | Pressure Control | Vented to VRS |
| h. | Temperature Control | Operated at ambient temperature |
| i. | Liquid Level Indicators | Gage/board system on tank |
| j. | Vapor Control System and Tank Venting | Vapor recovery |
| k. | Labels Identifying Contents | NFPA and Tank No. |
| l. | Joints | Welded seams |
| m. | Welds | External |
| n. | Plumbing | |
| o. | Pumps | |
| p. | Pumping Rates | |
| q. | Lightning Protection | None |
| r. | Other Features | |
| | | |
| 4. | Waste Stored and Impact | |
| a. | Type and Characteristics | Waste antifreeze (ethylene glycol) solutions |
| b. | S.G. of Wastes | .9 – 1.4 (1.04 for 50/50 mixture at 20° C. |
| c. | Layers of Wastes | 3 separate phases possible |
| d. | Compatibility With Tank or Liner | Wastes are fully compatible with tank. |



TANK DATA SHEET

Existing Hazardous Waste Storage or Treatment Tank

Tank No. T-512A
Designated Use: Bobtail Preselection

1. Tank Information
 - a. Design Specifications
 1. Referenced design standard UL 142
 2. Dimensions (Diameter and Height (ft)) 11'11" x 12'0 "
 3. Capacity (gallons) 10,000
 4. Shell thickness (inches) and corrosion allowance 3/16" 1/8"
 5. Pressure rating
Design (psig) Atmospheric
Operating (psig) Atmospheric
 6. Structural Supports Bolted to Concrete Slab
 7. Roof design Conical
 8. Year constructed 1985
 9. Tank location Outside
 10. Tank orientation Vertical
 - b. Construction Materials Steel (A-36)
 - c. Lining Material
 1. Composition None
 2. Thickness None
 3. Extent of coverage N/A
 - d. Corrosion/erosion resistance
 1. To wastes Steel is compatible with noncorrosive oily wastes
 2. To weather Paint should provide adequate protection
 - e. Pertinent Characteristics
 1. Date tank went into service 1986
 2. Life expectancy of tank (years) 20+years starting 2001 See CONAM Inspection Report 12/03/01
 - f. Previous Use of Tank
 1. Material stored New 1986, waste oil stored since new
 2. Length of service 10 years
 - g. Drawing Certified by Engineer
2. Foundation Design Specifications
 - a. Foundation Material Con
 - b. Load Bearing Capacity
 - c. Fire Protection Rating Not stated, but design certified by registered engineer
 - d. Impact of Weather Tank design certified by registered engineer
 - e. Drawing Certified by Engineer
3. Ancillary Tank Equipment
 - a. Piping
 - 1) Feed 4"
 - 2) Discharge 6"



EOI RCRA Part B Permit Application
Revision 4 – August 2003

- | | | |
|----|---------------------------------------|--|
| b. | Instrumentation | High level alarm |
| c. | Process Flow Diagram | |
| d. | Feed Systems | |
| e. | Waste Feed Cutoff | Manual |
| f. | Bypass System | Overflow to X-508 |
| g. | Pressure Control | Vented to VRS |
| h. | Temperature Control | Operated at ambient temperature |
| i. | Liquid Level Indicators | Gage/board system on tank |
| j. | Vapor Control System and Tank Venting | Vented to VRS |
| k. | Labels Identifying Contents | NFPA and Tank No. |
| l. | Joints | Welded seams |
| m. | Welds | External |
| n. | Plumbing | |
| o. | Pumps | |
| p. | Pumping Rates | |
| q. | Lightning Protection | None |
| r. | Other Features | |
| 4. | Waste Stored and Impact | |
| a. | Type and Characteristics | Used Oil/Recycled Oil |
| b. | S.G. of Wastes | .8 to 1.1 |
| c. | Layers of Wastes | 3 separate phases possible |
| d. | Compatibility With Tank or Liner | Wastes are fully compatible with tank. |



TANK DATA SHEET

Existing Hazardous Waste Storage or Treatment Tank

Tank No. T-512B
Designated Use: Bobtail Preselection

1. Tank Information
 - a. Design Specifications
 1. Referenced design standard UL 142
 2. Dimensions (Diameter and Height (ft)) 11'11" x 12'0 "
 3. Capacity (gallons) 10,000
 4. Shell thickness (inches) 3/16"
 - and corrosion allowance 1/8"
 5. Pressure rating
Design (psig) Atmospheric
Operating (psig) Atmospheric
 6. Structural Supports Bolted to Concrete Slab
 7. Roof design Conical
 8. Year constructed 1985
 9. Tank location Outside
 10. Tank orientation Vertical
 - b. Construction Materials Steel (A-36)
 - c. Lining Material
 1. Composition None
 2. Thickness None
 3. Extent of coverage N/A
 - d. Corrosion/erosion resistance
 1. To wastes Steel is compatible with noncorrosive oily wastes
Paint should provide adequate protection
 2. To weather
 - e. Pertinent Characteristics
 1. Date tank went into service 1986
 2. Life expectancy of tank (years) 20+years starting 2001 See CONAM Inspection Report 12/03/01
 - f. Previous Use of Tank
 1. Material stored New 1986, waste oil stored since new
 2. Length of service 10 years
 - g. Drawing Certified by Engineer
2. Foundation Design Specifications
 - a. Foundation Material Con
 - b. Load Bearing Capacity
 - c. Fire Protection Rating Not stated, but design certified by registered engineer
 - d. Impact of Weather Tank design certified by registered engineer
 - e. Drawing Certified by Engineer
3. Ancillary Tank Equipment
 - a. Piping
 - 1) Feed 4"
 - 2) Discharge 6"



EOI RCRA Part B Permit Application
Revision 4 – August 2003

- | | | |
|----|---------------------------------------|--|
| b. | Instrumentation | High level alarm |
| c. | Process Flow Diagram | |
| d. | Feed Systems | |
| e. | Waste Feed Cutoff | Manual |
| f. | Bypass System | Overflow to X-508 |
| g. | Pressure Control | Vented to VRS |
| h. | Temperature Control | Operated at ambient temperature |
| i. | Liquid Level Indicators | Gage/board system on tank |
| j. | Vapor Control System and Tank Venting | Vented to VRS |
| k. | Labels Identifying Contents | NFPA and Tank No. |
| l. | Joints | Welded seams |
| m. | Welds | External |
| n. | Plumbing | |
| o. | Pumps | |
| p. | Pumping Rates | |
| q. | Lightning Protection | None |
| r. | Other Features | |
| 4. | Waste Stored and Impact | |
| a. | Type and Characteristics | Used Oil/Recycled Oil |
| b. | S.G. of Wastes | .8 to 1.1 |
| c. | Layers of Wastes | 3 separate phases possible |
| d. | Compatibility With Tank or Liner | Wastes are fully compatible with tank. |



TANK DATA SHEET

Existing Hazardous Waste Storage or Treatment Tank

Tank No. T-502
Designated Use: Waste Oil Fuel Blending

1. Tank Information
 - a. Design Specifications
 1. Referenced design standard API 650 & Appendix E
 2. Dimensions (Diameter and Height (ft)) 20'8" x 20'0 "
 3. Capacity (gallons) 50,000
 4. Shell thickness (inches) 3/16"
 - and corrosion allowance 1/8"
 5. Pressure rating
Design (psig) Atmospheric
Operating (psig) Atmospheric
 6. Structural Supports Bolted to Concrete Slab
 7. Roof design Conical
 8. Year constructed 1985
 9. Tank location Outside
 10. Tank orientation Vertical
 - b. Construction Materials Steel (A-283C)
 - c. Lining Material
 1. Composition None
 2. Thickness None
 3. Extent of coverage N/A
 - d. Corrosion/erosion resistance
 1. To wastes Steel is compatible with oil mixtures
 2. To weather Paint should provide adequate protection
 - e. Pertinent Characteristics
 1. Date tank went into service 1986
 2. Life expectancy of tank (years) 20 years (to be adjusted, based on periodic integrity testing)
 - f. Previous Use of Tank
 1. Material stored New 1986, oil or waste oil since new
 2. Length of service 10 years
 - g. Drawing Certified by Engineer
2. Foundation Design Specifications
 - a. Foundation Material Concrete slab
 - b. Load Bearing Capacity
 - c. Fire Protection Rating Not stated, but design certified by registered engineer
 - d. Impact of Weather Tank design certified by registered engineer
 - e. Drawing Certified by Engineer
3. Ancillary Tank Equipment
 - a. Piping
 - 1) Feed 4"
 - 2) Discharge 6"
 - b. Instrumentation High level alarm
 - c. Process Flow Diagram



EOI RCRA Part B Permit Application
Revision 4 – May 2003

- | | | |
|----|---------------------------------------|--|
| d. | Feed Systems | |
| e. | Waste Feed Cutoff | Manual |
| f. | Bypass System | Overflow to diked containment |
| g. | Pressure Control | Vented to atmosphere |
| h. | Temperature Control | Operated at ambient temperature |
| i. | Liquid Level Indicators | Gage/board system on tank |
| j. | Vapor Control System and Tank Venting | Vented to VRS |
| k. | Labels Identifying Contents | NFPA and Tank No. |
| l. | Joints | Welded seams |
| m. | Welds | External |
| n. | Plumbing | |
| o. | Pumps | |
| p. | Pumping Rates | |
| q. | Lightning Protection | None |
| r. | Other Features | |
| | | |
| 4. | Waste Stored and Impact | |
| a. | Type and Characteristics | Used Oil/Recycled Oil/Waste Oil |
| b. | S.G. of Wastes | .8 to 1.0 |
| c. | Layers of Wastes | 3 separate phases possible, but not likely |
| d. | Compatibility With Tank or Liner | Wastes are fully compatible with tank. |



TANK DATA SHEET

Existing Hazardous Waste Storage or Treatment Tank

Tank No. T-503A

Designated Use: Waste Oil Feed Tank

1. Tank Information

a. Design Specifications

- | | | |
|-----|---------------------------------------|---|
| 1. | Referenced design standard | API 650 & Appendix E |
| 2. | Dimensions (Diameter and Height (ft)) | 33'8" x 30'0" |
| 3. | Capacity (gallons) | 200,000 |
| 4. | Shell thickness (inches) | 4 Rings:
(1) 0.23";(2)0.205";(3)3/16";(4)3/16" |
| | and corrosion allowance | 1/8" |
| 5. | Pressure rating | |
| | Design (psig) | Atmospheric |
| | Operating (psig) | Atmospheric |
| 6. | Structural Supports | Bolted to Concrete Slab |
| 7. | Roof design | Conical |
| 8. | Year constructed | 1985 |
| 9. | Tank location | Outside |
| 10. | Tank orientation | Vertical |

b. Construction Materials

Steel: Sides (A-516-70, A36, A-283-C)
Floor and roof: A-283-C

c. Lining Material

- | | | |
|----|--------------------|------|
| 1. | Composition | None |
| 2. | Thickness | None |
| 3. | Extent of coverage | N/A |

d. Corrosion/erosion resistance

- | | | |
|----|------------|--|
| 1. | To wastes | Steel is compatible with oil mixtures |
| 2. | To weather | Paint should provide adequate protection |

e. Pertinent Characteristics

- | | | |
|----|---------------------------------|---|
| 1. | Date tank went into service | 1986 |
| 2. | Life expectancy of tank (years) | 20+ years starting 2001 See CONAM
Inspection Report 12/03/01 |

f. Previous Use of Tank

- | | | |
|----|-------------------|--------------------------------------|
| 1. | Material stored | New 1986, waste oil stored since new |
| 2. | Length of service | 10 years |

g. Drawing Certified by Engineer

2. Foundation Design Specifications

- | | | |
|----|-------------------------------|--|
| a. | Foundation Material | Concrete slab |
| b. | Load Bearing Capacity | |
| c. | Fire Protection Rating | Not stated, but design certified by registered
engineer |
| d. | Impact of Weather | Tank design certified by registered engineer |
| e. | Drawing Certified by Engineer | |

3. Ancillary Tank Equipment

a. Piping

- | | | |
|----|-----------|----|
| 1) | Feed | 4" |
| 2) | Discharge | 6" |



EOI RCRA Part B Permit Application
Revision 4 – August 2003

- | | | |
|----|---------------------------------------|--|
| b. | Instrumentation | None |
| c. | Process Flow Diagram | |
| d. | Feed Systems | |
| e. | Waste Feed Cutoff | Manual |
| f. | Bypass System | Overflow to diked containment |
| g. | Pressure Control | Vented to VRS |
| h. | Temperature Control | Operated at ambient temperature |
| i. | Liquid Level Indicators | Gage/board system on tank |
| j. | Vapor Control System and Tank Venting | Vented to VRS |
| k. | Labels Identifying Contents | NFPA and Tank No. |
| l. | Joints | Welded seams |
| m. | Welds | External |
| n. | Plumbing | |
| o. | Pumps | |
| p. | Pumping Rates | |
| q. | Lightning Protection | None |
| r. | Other Features | |
| | | |
| 4. | Waste Stored and Impact | |
| a. | Type and Characteristics | Used Oil/Recycled Oil |
| b. | S.G. of Wastes | .8 to 1.0 |
| c. | Layers of Wastes | 1 |
| d. | Compatibility With Tank or Liner | Wastes are fully compatible with tank. |



TANK DATA SHEET

Existing Hazardous Waste Storage or Treatment Tank

Tank No. T-503B

Designated Use: Recycled Oil

1. Tank Information
 - a. Design Specifications
 1. Referenced design standard API 650 & Appendix E
 2. Dimensions (Diameter and Height (ft)) 33'8" x 30'0"
 3. Capacity (gallons) 200,000
 4. Shell thickness (inches) 4 Rings:
(1) 0.23";(2)0.205";(3)3/16";(4)3/16"
and corrosion allowance 1/8"
 5. Pressure rating
Design (psig) Atmospheric
Operating (psig) Atmospheric
 6. Structural Supports Bolted to Concrete Slab
 7. Roof design Conical
 8. Year constructed 1985
 9. Tank location Outside
 10. Tank orientation Vertical
 - b. Construction Materials
Steel: Sides (A-516-70, A36, A-283-C)
Floor and roof: A-283-C
 - c. Lining Material
 1. Composition None
 2. Thickness None
 3. Extent of coverage N/A
 - d. Corrosion/erosion resistance
 1. To wastes Steel is compatible with oil mixtures
 2. To weather Paint should provide adequate protection
 - e. Pertinent Characteristics
 1. Date tank went into service 1986
 2. Life expectancy of tank (years) 20+years starting 2001 See CONAM
Inspection Report 12/03/01
 - f. Previous Use of Tank
 1. Material stored New 1986, waste oil stored since new
 2. Length of service 10 years
 - g. Drawing Certified by Engineer
2. Foundation Design Specifications
 - a. Foundation Material Concrete slab
 - b. Load Bearing Capacity
 - c. Fire Protection Rating Not stated, but design certified by registered
engineer
 - d. Impact of Weather Tank design certified by registered engineer
 - e. Drawing Certified by Engineer
3. Ancillary Tank Equipment
 - a. Piping
 - 1) Feed 4"
 - 2) Discharge 4"



EOI RCRA Part B Permit Application
Revision 5 – August 2003

- | | | |
|----|---------------------------------------|--|
| b. | Instrumentation | None |
| c. | Process Flow Diagram | |
| d. | Feed Systems | |
| e. | Waste Feed Cutoff | Manual |
| f. | Bypass System | Overflow to X-508 |
| g. | Pressure Control | Vented to VRS |
| h. | Temperature Control | Operated at ambient temperature |
| I. | Liquid Level Indicators | Gage/board system on tank |
| j. | Vapor Control System and Tank Venting | Vented to VRS |
| k. | Labels Identifying Contents | NFPA and Tank No. |
| l. | Joints | Welded seams |
| m. | Welds | External |
| n. | Plumbing | |
| o. | Pumps | |
| p. | Pumping Rates | |
| q. | Lightning Protection | None |
| r. | Other Features | |
| 4. | Waste Stored and Impact | |
| a. | Type and Characteristics | Recycled Oil |
| b. | S.G. of Wastes | .8 to 1.0 |
| c. | Layers of Wastes | 1 |
| d. | Compatibility With Tank or Liner | Wastes are fully compatible with tank. |



TANK DATA SHEET

Existing Hazardous Waste Storage or Treatment Tank

Tank No. T-505

Designated Use: Used Oil/Recycled Oil

1. Tank Information
 - a. Design Specifications
 1. Referenced design standard API 650 & Appendix E
 2. Dimensions (Diameter and Height (ft)) 20'8" x 20'
 3. Capacity (gallons) 50,000
 4. Shell thickness (inches) 3/16"
 - and corrosion allowance 1/8"
 5. Pressure rating
Design (psig) Atmospheric
Operating (psig) Atmospheric
 6. Structural Supports Bolted to Concrete Slab
 7. Roof design Conical
 8. Year constructed 1985
 9. Tank location Outside
 10. Tank orientation Vertical
 - b. Construction Materials Steel: (A-283-C)
 - c. Lining Material
 1. Composition None
 2. Thickness None
 3. Extent of coverage N/A
 - d. Corrosion/erosion resistance
 1. To wastes Steel is compatible with oil mixtures
 2. To weather Paint should provide adequate protection
 - e. Pertinent Characteristics
 1. Date tank went into service 1986
 2. Life expectancy of tank (years) 20 years (to be adjusted, based on periodic integrity testing)
 - f. Previous Use of Tank
 1. Material stored New 1986, waste oil stored since new
 2. Length of service 10 years
 - g. Drawing Certified by Engineer
2. Foundation Design Specifications
 - a. Foundation Material Concrete slab
 - b. Load Bearing Capacity
 - c. Fire Protection Rating Not stated, but design certified by registered engineer
 - d. Impact of Weather Tank design certified by registered engineer
 - e. Drawing Certified by Engineer
3. Ancillary Tank Equipment
 - a. Piping
 - 1) Feed 4"
 - 2) Discharge 6"
 - b. Instrumentation High Level Alarm, Temperature Indicator
 - c. Process Flow Diagram



EOI RCRA Part B Permit Application
Revision 4 – May 2003

- | | | |
|----|---------------------------------------|--|
| d. | Feed Systems | Manual |
| e. | Waste Feed Cutoff | Overflow to X-508 |
| f. | Bypass System | Vented to atmosphere |
| g. | Pressure Control | Operated at ambient temperature |
| h. | Temperature Control | Gage/board system on tank |
| i. | Liquid Level Indicators | Vented to VRS |
| j. | Vapor Control System and Tank Venting | NFPA and Tank No. |
| k. | Labels Identifying Contents | Welded seams |
| l. | Joints | External |
| m. | Welds | |
| n. | Plumbing | |
| o. | Pumps | |
| p. | Pumping Rates | |
| q. | Lightning Protection | None |
| r. | Other Features | |
| 4. | Waste Stored and Impact | |
| a. | Type and Characteristics | Used Oil/Recycled Oil |
| b. | S.G. of Wastes | .8 to 1.0 |
| c. | Layers of Wastes | 3 separate phases possible, but not likely |
| d. | Compatibility With Tank or Liner | Wastes are fully compatible with tank. |



TANK DATA SHEET

Existing Hazardous Waste Storage or Treatment Tank

Tank No. T-507

Designated Use: Waste Oil Storage (SB 86 Certified Oil)

1. Tank Information

a. Design Specifications

- | | |
|--|-------------------------|
| 1. Referenced design standard | API 650 & Appendix E |
| 2. Dimensions (Diameter and Height (ft)) | 20'8" x 20' |
| 3. Capacity (gallons) | 50,000 |
| 4. Shell thickness (inches)
and corrosion allowance | 3/16"
1/8" |
| 5. Pressure rating | |
| Design (psig) | Atmospheric |
| Operating (psig) | Atmospheric |
| 6. Structural Supports | Bolted to Concrete Slab |
| 7. Roof design | Conical |
| 8. Year constructed | 1985 |
| 9. Tank location | Outside |
| 10. Tank orientation | Vertical |

b. Construction Materials

Steel (A-283-C)

c. Lining Material

- | | |
|-----------------------|------|
| 1. Composition | None |
| 2. Thickness | None |
| 3. Extent of coverage | N/A |

d. Corrosion/erosion resistance

- | | |
|---------------|--|
| 1. To wastes | Steel is compatible with oil mixtures |
| 2. To weather | Paint should provide adequate protection |

e. Pertinent Characteristics

- | | |
|------------------------------------|--|
| 1. Date tank went into service | 1986 |
| 2. Life expectancy of tank (years) | 20+years starting 2001 See CONAM
Inspection Report 12/03/01 |

f. Previous Use of Tank

- | | |
|----------------------|--------------------------------------|
| 1. Material stored | New 1986, oil or waste oil since new |
| 2. Length of service | 10 years |

g. Drawing Certified by Engineer

2. Foundation Design Specifications

- | | |
|----------------------------------|---|
| a. Foundation Material | Concrete slab |
| b. Load Bearing Capacity | |
| c. Fire Protection Rating | Not stated, but design certified by registered engineer |
| d. Impact of Weather | Tank design certified by registered engineer |
| e. Drawing Certified by Engineer | |

3. Ancillary Tank Equipment

- | | |
|--------------------|------------------|
| a. Piping | |
| 1) Feed | 4" |
| 2) Discharge | 6" |
| b. Instrumentation | High Level Alarm |



EOI RCRA Part B Permit Application
Revision 4 – August 2003

- | | | |
|----|---------------------------------------|---|
| c. | Process Flow Diagram | |
| d. | Feed Systems | |
| e. | Waste Feed Cutoff | Manual |
| f. | Bypass System | Overflow to diked containment |
| g. | Pressure Control | Vented to VRS |
| h. | Temperature Control | Operated at ambient temperature |
| i. | Liquid Level Indicators | Gage/board system on tank |
| j. | Vapor Control System and Tank Venting | Vented to carbon cannisters |
| k. | Labels Identifying Contents | NFPA and Tank No. |
| l. | Joints | Welded seams |
| m. | Welds | External |
| n. | Plumbing | |
| o. | Pumps | |
| p. | Pumping Rates | |
| q. | Lightning Protection | None |
| r. | Other Features | May be nitrogen blanketed |
| 4. | Waste Stored and Impact | |
| a. | Type and Characteristics | Used Oil/Recycled Oil |
| b. | S.G. of Wastes | .8 - 1.0 |
| c. | Layers of Wastes | 3 separate phases possible,
but not likely |
| d. | Compatibility With Tank or Liner | Wastes are fully compatible with tank. |



TANK DATA SHEET

Existing Hazardous Waste Storage or Treatment Tank

Tank No. T-509
Designated Use: Used Oil/Recycled Oil

1. Tank Information

a. Design Specifications

- | | |
|--|-------------------------|
| 1. Referenced design standard | UL 142 |
| 2. Dimensions (Diameter and Height (ft)) | 13'6" x 24'0 " |
| 3. Capacity (gallons) | 25,000 |
| 4. Shell thickness (inches)
and corrosion allowance | 3/16"
1/8" |
| 5. Pressure rating | |
| Design (psig) | Atmospheric |
| Operating (psig) | Atmospheric |
| 6. Structural Supports | Bolted to Concrete Slab |
| 7. Roof design | Conical |
| 8. Year constructed | 1985 |
| 9. Tank location | Outside |
| 10. Tank orientation | Vertical |

b. Construction Materials

Steel (A-283-C)

c. Lining Material

- | | |
|-----------------------|------|
| 1. Composition | None |
| 2. Thickness | None |
| 3. Extent of coverage | N/A |

d. Corrosion/erosion resistance

- | | |
|---------------|--|
| 1. To wastes | Steel is compatible with oil mixtures |
| 2. To weather | Paint should provide adequate protection |

e. Pertinent Characteristics

- | | |
|------------------------------------|--|
| 1. Date tank went into service | 1986 |
| 2. Life expectancy of tank (years) | 20+years starting 2001 See CONAM
Inspection Report 12/03/01 |

f. Previous Use of Tank

- | | |
|----------------------|-------------------------|
| 1. Material stored | New 1986, oil since new |
| 2. Length of service | 10 years |

g. Drawing Certified by Engineer

2. Foundation Design Specifications

- | | |
|----------------------------------|--|
| a. Foundation Material | Concrete slab |
| b. Load Bearing Capacity | |
| c. Fire Protection Rating | Not stated, but design certified by registered
engineer |
| d. Impact of Weather | Tank design certified by registered engineer |
| e. Drawing Certified by Engineer | |

3. Ancillary Tank Equipment

- | | |
|--------------------|------|
| a. Piping | |
| 1) Feed | 4" |
| 2) Discharge | 6" |
| b. Instrumentation | None |



EOI RCRA Part B Permit Application
Revision 5 -- August 2003

- | | | |
|----|---------------------------------------|--|
| c. | Process Flow Diagram | |
| d. | Feed Systems | |
| e. | Waste Feed Cutoff | Manual |
| f. | Bypass System | Overflow to diked containment area |
| g. | Pressure Control | Vented to VRS |
| h. | Temperature Control | Operated at ambient temperature |
| i. | Liquid Level Indicators | Gage/board system on tank |
| j. | Vapor Control System and Tank Venting | Vented to VRS |
| k. | Labels Identifying Contents | NFPA and Tank No. |
| l. | Joints | Welded seams |
| m. | Welds | External |
| n. | Plumbing | |
| o. | Pumps | |
| p. | Pumping Rates | |
| q. | Lightning Protection | None |
| r. | Other Features | |
| 4. | Waste Stored and Impact | |
| a. | Type and Characteristics | Used Oil/Recycled Oil |
| b. | S.G. of Wastes | .8 to 1.0 |
| c. | Layers of Wastes | 3 separate phases possible |
| d. | Compatibility With Tank or Liner | Wastes are fully compatible with tank. |



TANK DATA SHEET

Existing Hazardous Waste Storage or Treatment Tank

Tank No. T-651A

Designated Use: Wastewater

1. Tank Information

a. Design Specifications

- | | | |
|-----|---|-------------------------|
| 1. | Referenced design standard | UL 142 |
| 2. | Dimensions (Diameter and Height (ft)) | 14' x 27' |
| 3. | Capacity (gallons) | 31,000 |
| 4. | Shell thickness (inches)
and corrosion allowance | 3/16"
1/8" |
| 5. | Pressure rating | |
| | Design (psig) | Atmospheric |
| | Operating (psig) | Atmospheric |
| 6. | Structural Supports | Bolted to Concrete Slab |
| 7. | Roof design | Conical |
| 8. | Year constructed | 1986 |
| 9. | Tank location | Outside |
| 10. | Tank orientation | Vertical |

b. Construction Materials

Steel (A-283-C)

c. Lining Material

- | | | |
|----|--------------------|------|
| 1. | Composition | None |
| 2. | Thickness | None |
| 3. | Extent of coverage | N/A |

d. Corrosion/erosion resistance

- | | | |
|----|------------|---|
| 1. | To wastes | Steel is compatible with oily wastewater mixtures |
| 2. | To weather | Paint should provide adequate protection |

e. Pertinent Characteristics

- | | | |
|----|---------------------------------|---|
| 1. | Date tank went into service | 1987 |
| 2. | Life expectancy of tank (years) | 20+years starting 2001 See CONAM Inspection Report 12/03/01 |

f. Previous Use of Tank

- | | | |
|----|-------------------|--------------------------------|
| 1. | Material stored | New 1986, wastewater since new |
| 2. | Length of service | 9 years |

g. Drawing Certified by Engineer

See Attachment IV-3

2. Foundation Design Specifications

a. Foundation Material

Concrete slab

b. Load Bearing Capacity

c. Fire Protection Rating

Not stated, but design certified by registered engineer

d. Impact of Weather

e. Drawing Certified by Engineer

Tank design certified by registered engineer

3. Ancillary Tank Equipment

a. Piping

- | | | |
|----|-----------|----|
| 1) | Feed | 4" |
| 2) | Discharge | 6" |

b. Instrumentation

None



EOI RCRA Part B Permit Application
Revision 4 – August 2003

- | | | |
|----|---------------------------------------|--|
| c. | Process Flow Diagram | |
| d. | Feed Systems | |
| e. | Waste Feed Cutoff | Manual |
| f. | Bypass System | Overflow to diked containment area |
| g. | Pressure Control | Vented to VRS |
| h. | Temperature Control | Operated at ambient temperature |
| i. | Liquid Level Indicators | Gage/board system on tank |
| j. | Vapor Control System and Tank Venting | Vented to VRS |
| k. | Labels Identifying Contents | NFPA and Tank No. |
| l. | Joints | Welded seams |
| m. | Welds | External |
| n. | Plumbing | |
| o. | Pumps | |
| p. | Pumping Rates | |
| q. | Lightning Protection | None |
| r. | Other Features | |
| 4. | Waste Stored and Impact | |
| a. | Type and Characteristics | Used Oil/Wastewater |
| b. | S.G. of Wastes | .8 to 1.4 |
| c. | Layers of Wastes | 3 separate phases possible |
| d. | Compatibility With Tank or Liner | Wastes are fully compatible with tank. |



TANK DATA SHEET

Existing Hazardous Waste Storage or Treatment Tank

Tank No. T-651B
Designated Use: Wastewater

1. Tank Information
 - a. Design Specifications
 1. Referenced design standard UL 142
 2. Dimensions (Diameter and Height (ft)) 14' x 27'
 3. Capacity (gallons) 31,000
 4. Shell thickness (inches) 3/16"
 - and corrosion allowance 1/8"
 5. Pressure rating
Design (psig) Atmospheric
Operating (psig) Atmospheric
 6. Structural Supports Bolted to Concrete Slab
 7. Roof design Conical
 8. Year constructed 1986
 9. Tank location Outside
 10. Tank orientation Vertical
 - b. Construction Materials Steel (A-283-C)
 - c. Lining Material
 1. Composition None
 2. Thickness None
 3. Extent of coverage N/A
 - d. Corrosion/erosion resistance
 1. To wastes Steel is compatible with oily wastewater mixtures
 2. To weather Paint should provide adequate protection
 - e. Pertinent Characteristics
 1. Date tank went into service 1987
 2. Life expectancy of tank (years) 20+years starting 2001 See CONAM Inspection Report 12/03/01
 - f. Previous Use of Tank
 1. Material stored New 1986, wastewater since new
 2. Length of service 9 years
 - g. Drawing Certified by Engineer
2. Foundation Design Specifications
 - a. Foundation Material Concrete slab
 - b. Load Bearing Capacity
 - c. Fire Protection Rating Not stated, but design certified by registered engineer
 - d. Impact of Weather Tank design certified by registered engineer
 - e. Drawing Certified by Engineer
3. Ancillary Tank Equipment
 - a. Piping
 - 1) Feed 4"
 - 2) Discharge 6"
 - b. Instrumentation None



EOI RCRA Part B Permit Application
Revision 4 – August 2003

- | | | |
|----|---------------------------------------|--|
| c. | Process Flow Diagram | |
| d. | Feed Systems | |
| e. | Waste Feed Cutoff | Manual |
| f. | Bypass System | Overflow to diked containment area |
| g. | Pressure Control | Vented to VRS |
| h. | Temperature Control | Operated at ambient temperature |
| i. | Liquid Level Indicators | Gage/board system on tank |
| j. | Vapor Control System and Tank Venting | Vented to VRS |
| k. | Labels Identifying Contents | NFPA and Tank No. |
| l. | Joints | Welded seams |
| m. | Welds | External |
| n. | Plumbing | |
| o. | Pumps | |
| p. | Pumping Rates | |
| q. | Lightning Protection | None |
| r. | Other Features | |
| | | |
| 4. | Waste Stored and Impact | |
| a. | Type and Characteristics | Used Oil/Wastewater |
| b. | S.G. of Wastes | .8 to 1.4 |
| c. | Layers of Wastes | 3 separate phases possible |
| d. | Compatibility With Tank or Liner | Wastes are fully compatible with tank. |



TANK DATA SHEET

Existing Hazardous Waste Storage or Treatment Tank

Tank No. T-652
Designated Use: Wastewater Storage

1. Tank Information

- a. Design Specifications
 - 1. Referenced design standard UL 142
 - 2. Dimensions (Diameter and Height (ft)) 11'11" x 12'0"
 - 3. Capacity (gallons) 10,000
 - 4. Shell thickness (inches) 3/16"
 - and corrosion allowance 1/8"
 - 5. Pressure rating
 - Design (psig) Atmospheric
 - Operating (psig) Atmospheric
 - 6. Structural Supports Bolted to Concrete Slab
 - 7. Roof design Conical
 - 8. Year constructed 1986
 - 9. Tank location Outside
 - 10. Tank orientation Vertical
- b. Construction Materials Steel (A-36)
- c. Lining Material
 - 1. Composition None
 - 2. Thickness None
 - 3. Extent of coverage N/A
- d. Corrosion/erosion resistance
 - 1. To wastes Steel is compatible with noncorrosive oily aqueous wastes
 - 2. To weather Paint should provide adequate protection
- e. Pertinent Characteristics
 - 1. Date tank went into service 1986
 - 2. Life expectancy of tank (years) 20+years starting 2001 See CONAM Inspection Report 12/03/01
- f. Previous Use of Tank
 - 1. Material stored New 1987, wastewater stored since new
 - 2. Length of service 9 years
- g. Drawing Certified by Engineer

2. Foundation Design Specifications

- a. Foundation Material Concrete slab
- b. Load Bearing Capacity
- c. Fire Protection Rating Not stated, but design certified by registered engineer
- d. Impact of Weather Tank design certified by registered engineer
- e. Drawing Certified by Engineer

3. Ancillary Tank Equipment

- a. Piping
 - 1) Feed 4"
 - 2) Discharge 6"



EOI RCRA Part B Permit Application
Revision 4 – August 2003

- | | | |
|----|---------------------------------------|--|
| b. | Instrumentation | None |
| c. | Process Flow Diagram | |
| d. | Feed Systems | |
| e. | Waste Feed Cutoff | Manual |
| f. | Bypass System | Overflow to X-508 |
| g. | Pressure Control | Vented to VRS |
| h. | Temperature Control | Operated at ambient temperature |
| i. | Liquid Level Indicators | Gage/board system on tank |
| j. | Vapor Control System and Tank Venting | Vented to VRS |
| k. | Labels Identifying Contents | NFPA and Tank No. |
| l. | Joints | Welded seams |
| m. | Welds | External |
| n. | Plumbing | |
| o. | Pumps | |
| p. | Pumping Rates | |
| q. | Lightning Protection | None |
| r. | Other Features | |
| 4. | Waste Stored and Impact | |
| a. | Type and Characteristics | Used Oil/Wastewater |
| b. | S.G. of Wastes | .9 to 1.4 |
| c. | Layers of Wastes | 3 separate phases possible |
| d. | Compatibility With Tank or Liner | Wastes are fully compatible with tank. |



TANK DATA SHEET

Existing Hazardous Waste Storage or Treatment Tank

Tank No. T-704A
Designated Use: Wastewater

1. Tank Information
 - a. Design Specifications
 1. Referenced design standard
 2. Dimensions (Diameter and Height (ft)) 12' x 10' 10 3/4"
 3. Capacity (gallons) 7000
 4. Shell thickness (inches) 3/8
 - and corrosion allowance Not Applicable
 5. Pressure rating
 - Design (psig) Atmospheric
 - Operating (psig) Atmospheric
 6. Structural Supports Anchored by cables
 7. Roof design Molded one-piece integral with tank
 8. Year constructed 1987
 9. Tank location Tank Farm
 10. Tank orientation Vertical
 - b. Construction Materials High density polyethylene
 - c. Lining Material
 1. Composition None
 2. Thickness N/A
 3. Extent of coverage N/A
 - d. Corrosion/erosion resistance
 1. To wastes Polyethylene is compatible with a wide variety of organic compounds, as well as acids and bases
 2. To weather Stabilized against UV degradation
 - e. Pertinent Characteristics
 1. Date tank went into service 1987
 2. Life expectancy of tank (years) 20 years
 - f. Previous Use of Tank
 1. Material stored None, tank new in 1987
 2. Length of service 11 years
 - g. Drawing Certified by Engineer
2. Foundation Design Specifications
 - a. Foundation Material Reinforced concrete
 - b. Load Bearing Capacity See Attachment IV-4
 - c. Fire Protection Rating Not stated, but design certified by registered engineer
 - d. Impact of Weather Tank design certified by registered engineer
 - e. Drawing Certified by Engineer



EOI RCRA Part B Permit Application
Revision 2 – May 29, 1998

- | | | |
|----|---------------------------------------|--|
| 3. | Ancillary Tank Equipment | |
| a. | Piping | |
| | 1) Feed | 2" |
| | 2) Discharge | 2" |
| b. | Instrumentation | High level alarm |
| c. | Process Flow Diagram | |
| d. | Feed Systems | |
| e. | Waste Feed Cutoff | Manual |
| f. | Bypass System | Overflow to X-508 |
| g. | Pressure Control | Vented to atmosphere |
| h. | Temperature Control | Operated at ambient temperature |
| i. | Liquid Level Indicators | Gage/board system |
| j. | Vapor Control System and Tank Venting | Vented to atmosphere |
| k. | Labels Identifying Contents | NFPA and Tank No. |
| l. | Joints | Molded one-piece |
| m. | Welds | N/A |
| n. | Plumbing | |
| o. | Pumps | |
| p. | Pumping Rates | |
| q. | Lightning Protection | None |
| r. | Other Features | N/A |
| 4. | Waste Stored and Impact | |
| a. | Type and Characteristics | Wastewater |
| b. | S.G. of Wastes | 1.0 to 1.4 |
| c. | Layers of Wastes | 3 separate phases possible |
| d. | Compatibility With Tank or Liner | Wastes are fully compatible with tank. |



TANK DATA SHEET

Existing Hazardous Waste Storage or Treatment Tank

Tank No. T-704B
Designated Use: Wastewater

1. Tank Information
 - a. Design Specifications
 1. Referenced design standard
 2. Dimensions (Diameter and Height (ft)) 12' x 10' 10 3/4"
 3. Capacity (gallons) 7000
 4. Shell thickness (inches) 3/8
 - and corrosion allowance Not Applicable
 5. Pressure rating
 - Design (psig) Atmospheric
 - Operating (psig) Atmospheric
 6. Structural Supports Anchored by cables
 7. Roof design Molded one-piece integral with tank
 8. Year constructed 1987
 9. Tank location Tank Farm
 10. Tank orientation Vertical
 - b. Construction Materials High density polyethylene
 - c. Lining Material
 1. Composition None
 2. Thickness N/A
 3. Extent of coverage N/A
 - d. Corrosion/erosion resistance
 1. To wastes Polyethylene is compatible with a wide variety of organic compounds, as well as acids and bases
 2. To weather Stabilized against UV degradation
 - e. Pertinent Characteristics
 1. Date tank went into service 1987
 2. Life expectancy of tank (years) 20 years
 - f. Previous Use of Tank
 1. Material stored None, tank new in 1987
 2. Length of service 11 years
 - g. Drawing Certified by Engineer
2. Foundation Design Specifications
 - a. Foundation Material Reinforced Concrete
 - b. Load Bearing Capacity
 - c. Fire Protection Rating Not stated, but design certified by registered engineer
 - d. Impact of Weather Tank design certified by registered engineer
 - e. Drawing Certified by Engineer



EOI RCRA Part B Permit Application
Revision 2 – May 29, 1998

3. Ancillary Tank Equipment
 - a. Piping
 - 1) Feed 2"
 - 2) Discharge 2"
 - b. Instrumentation High level alarm
 - c. Process Flow Diagram
 - d. Feed Systems
 - e. Waste Feed Cutoff Manual
 - f. Bypass System Overflow to X-508
 - g. Pressure Control Vented to atmosphere
 - h. Temperature Control Operated at ambient temperature
 - I. Liquid Level Indicators Gage/board system
 - j. Vapor Control System and Tank Venting Vented to atmosphere
 - k. Labels Identifying Contents NFPA and Tank No.
 - l. Joints Molded one-piece
 - m. Welds N/A
 - n. Plumbing
 - o. Pumps
 - p. Pumping Rates
 - q. Lightning Protection None
 - r. Other Features N/A
4. Waste Stored and Impact
 - a. Type and Characteristics Wastewater
 - b. S.G. of Wastes 1.0 to 1.4
 - c. Layers of Wastes 3 separate phases possible
 - d. Compatibility With Tank or Liner Wastes are fully compatible with tank.



TANK DATA SHEET

Existing Hazardous Waste Storage or Treatment Tank

Tank No. T-705A
Designated Use: Wastewater

1. Tank Information
 - a. Design Specifications
 1. Referenced design standard
 2. Dimensions (Diameter and Height (ft)) 12' x 10' 10 3/4"
 3. Capacity (gallons) 7,000
 4. Shell thickness (inches) 3/8"
 - and corrosion allowance Not Applicable
 5. Pressure rating
 - Design (psig) Atmospheric
 - Operating (psig) Atmospheric
 6. Structural Supports Anchored by cables
 7. Roof design Molded one-piece integral with tank
 8. Year constructed 1987
 9. Tank location Tank Farm
 10. Tank orientation Vertical
 - b. Construction Materials High density polyethylene
 - c. Lining Material
 1. Composition None
 2. Thickness N/A
 3. Extent of coverage N/A
 - d. Corrosion/erosion resistance
 1. To wastes Polyethylene is compatible with a wide variety of organic compounds, as well as acids and bases
 2. To weather Stabilized against UV degradation
 - e. Pertinent Characteristics
 1. Date tank went into service 1987
 2. Life expectancy of tank (years) 20 years
 - f. Previous Use of Tank
 1. Material stored None, tank new in 1987
 2. Length of service 11 years
 - g. Drawing Certified by Engineer
2. Foundation Design Specifications
 - a. Foundation Material Reinforced concrete
 - b. Load Bearing Capacity
 - c. Fire Protection Rating Not stated, but design certified by registered engineer
 - d. Impact of Weather Tank design certified by registered engineer



EOI RCRA Part B Permit Application
Revision 3 – March 2002

- | | | |
|----|---------------------------------------|--|
| e. | Drawing Certified by Engineer | |
| 3. | Ancillary Tank Equipment | |
| a. | Piping | |
| | 1) Feed | 2" |
| | 2) Discharge | 2" |
| b. | Instrumentation | High level alarm |
| c. | Process Flow Diagram | |
| d. | Feed Systems | |
| e. | Waste Feed Cutoff | Manual |
| f. | Bypass System | Overflow to X-508 |
| g. | Pressure Control | Vented to atmosphere |
| h. | Temperature Control | Operated at ambient temperature |
| I. | Liquid Level Indicators | Gage/board system |
| j. | Vapor Control System and Tank Venting | Vented to atmosphere |
| k. | Labels Identifying Contents | NFPA and Tank No. |
| l. | Joints | Molded one-piece |
| m. | Welds | N/A |
| n. | Plumbing | |
| o. | Pumps | |
| p. | Pumping Rates | |
| q. | Lightning Protection | None |
| r. | Other Features | |
| 4. | Waste Stored and Impact | |
| a. | Type and Characteristics | Wastewater |
| b. | S.G. of Wastes | 1.0 to 1.4 |
| c. | Layers of Wastes | 3 separate phases possible |
| d. | Compatibility With Tank or Liner | Wastes are fully compatible with tank. |



TANK DATA SHEET

Existing Hazardous Waste Storage or Treatment Tank

Tank No. T-705B

Designated Use: Wastewater

1. Tank Information

a. Design Specifications

1. Referenced design standard
2. Dimensions (Diameter and Height (ft)) 12' x 10'10 ¼"
3. Capacity (gallons) 7,000
4. Shell thickness (inches) 3/8"
- and corrosion allowance Not Applicable
5. Pressure rating
- Design (psig) Atmospheric
- Operating (psig) Atmospheric
6. Structural Supports Anchored by cables
7. Roof design Molded one-piece integral with tank
8. Year constructed 1987
9. Tank location Tank Farm
10. Tank orientation Vertical

b. Construction Materials

High density polyethylene

c. Lining Material

1. Composition None
2. Thickness N/A
3. Extent of coverage N/A

d. Corrosion/erosion resistance

1. To wastes Polyethylene is compatible with a wide variety of organic compounds, as well as acids and bases
2. To weather Stabilized against UV degradation

e. Pertinent Characteristics

1. Date tank went into service 1987
2. Life expectancy of tank (years) 20 years

f. Previous Use of Tank

1. Material stored None, tank new in 1987
2. Length of service 11 years

g. Drawing Certified by Engineer

2. Foundation Design Specifications

a. Foundation Material

Reinforced concrete

b. Load Bearing Capacity

c. Fire Protection Rating

Not stated, but design certified by registered engineer

d. Impact of Weather

Tank design certified by registered engineer



EOI RCRA Part B Permit Application
Revision 3 – March 2002

- | | | | |
|----|--------------------------|---------------------------------------|--|
| 3. | e. | Drawing Certified by Engineer | |
| | Ancillary Tank Equipment | | |
| | a. | Piping | |
| | | 1) Feed | 2" |
| | | 2) Discharge | 2" |
| | b. | Instrumentation | High level alarm |
| | c. | Process Flow Diagram | |
| | d. | Feed Systems | |
| | e. | Waste Feed Cutoff | Manual |
| | f. | Bypass System | Overflow to X-508- |
| | g. | Pressure Control | Vented to atmosphere |
| | h. | Temperature Control | Operated at ambient temperature |
| | i. | Liquid Level Indicators | Gage/board system |
| | j. | Vapor Control System and Tank Venting | Vented to atmosphere |
| | k. | Labels Identifying Contents | NFPA and Tank No. |
| | l. | Joints | Molded one-piece |
| | m. | Welds | N/A |
| | n. | Plumbing | |
| | o. | Pumps | |
| | p. | Pumping Rates | |
| | q. | Lightning Protection | None |
| | r. | Other Features | N/A |
| 4. | Waste Stored and Impact | | |
| | a. | Type and Characteristics | Nonhazardous Wastewater |
| | b. | S.G. of Wastes | 1.08 to 1.4 |
| | c. | Layers of Wastes | 3 separate phases possible |
| | d. | Compatibility With Tank or Liner | Wastes are fully compatible with tank. |



TANK DATA SHEET

Existing Hazardous Waste Storage or Treatment Tank

Tank No. T-705C
Designated Use: Wastewater

1. Tank Information
 - a. Design Specifications
 1. Referenced design standard
 2. Dimensions (Diameter and Height (ft)) 12' x 10' 10 3/4"
 3. Capacity (gallons) 7,000
 4. Shell thickness (inches) 3/8"
 - and corrosion allowance Not Applicable
 5. Pressure rating
 - Design (psig) Atmospheric
 - Operating (psig) Atmospheric
 6. Structural Supports Anchored by cables
 7. Roof design Molded one-piece integral with tank
 8. Year constructed 1987
 9. Tank location Tank Farm
 10. Tank orientation Vertical
 - b. Construction Materials High density polyethylene
 - c. Lining Material
 1. Composition None
 2. Thickness N/A
 3. Extent of coverage N/A
 - d. Corrosion/erosion resistance
 1. To wastes Polyethylene is compatible with a wide variety of organic compounds, as well as acids and bases
 2. To weather Stabilized against UV degradation
 - e. Pertinent Characteristics
 1. Date tank went into service 1987
 2. Life expectancy of tank (years) 20 years
 - f. Previous Use of Tank
 1. Material stored None, tank new in 1987
 2. Length of service 11 years
 - g. Drawing Certified by Engineer
2. Foundation Design Specifications
 - a. Foundation Material Reinforced concrete
 - b. Load Bearing Capacity
 - c. Fire Protection Rating Not stated, but design certified by registered engineer
 - d. Impact of Weather Tank design certified by registered engineer



EOI RCRA Part B Permit Application
Revision 3 – March 2002

- | | | |
|----|---------------------------------------|--|
| e. | Drawing Certified by Engineer | |
| 3. | Ancillary Tank Equipment | |
| a. | Piping | |
| | 1) Feed | 2" |
| | 2) Discharge | 2" |
| b. | Instrumentation | High level alarm |
| c. | Process Flow Diagram | |
| d. | Feed Systems | |
| e. | Waste Feed Cutoff | Manual |
| f. | Bypass System | Overflow to X-508 |
| g. | Pressure Control | Vented to atmosphere |
| h. | Temperature Control | Operated at ambient temperature |
| i. | Liquid Level Indicators | Gage/board system |
| j. | Vapor Control System and Tank Venting | Vented to atmosphere |
| k. | Labels Identifying Contents | NFPA and Tank No. |
| l. | Joints | Molded one-piece |
| m. | Welds | N/A |
| n. | Plumbing | |
| o. | Pumps | |
| p. | Pumping Rates | |
| q. | Lightning Protection | None |
| r. | Other Features | |
| 4. | Waste Stored and Impact | |
| a. | Type and Characteristics | Wastewater |
| b. | S.G. of Wastes | 1.0 to 1.4 |
| c. | Layers of Wastes | 3 separate phases possible |
| d. | Compatibility With Tank or Liner | Wastes are fully compatible with tank. |

